



**NOTES:**

- 1) PIPING SHOWN IN DASHED LINES - SUPPLIED BY CUSTOMER
- 2) ALLOW 1 FOOT ABOVE TANKS FOR LOADING
- 3) FLOW METER REQUIRES (15) PIPE DIAMETER LENGTHS BEFORE METER & (10) AFTER FOR PROPER OPERATION
- 4) FLOW METER SHOULD BE MOUNTED HORIZONTALLY

SHIPPING Wt.	2971 / 3554 Lbs.
OPERATING Wt.	.Lbs.

BY:	No.	REVISION	DATE	CHK'D
-	0	PRELIMINARY	08/08/2008	
	1	UPDATE BRINE TANK	03/23/2009	
	2	ADD TOP VIEW	10/22/2009	
	3	ADJUST PIPING	06/09/2010	
	4	MOVE BRINE TANK	02/25/2011	

**Water King**  
WATER CONDITIONING

WATER KING MF-300 / 450-S-2-TA SOFTENER TYPICAL PIPING ARRANGEMENT		
SCALE @ 24"x36"	DRAWING NUMBER	SHEET
N.T.S.	MF300-450-S2-TA	01 / 0 1
www.waterking.com		